

## Walnut Avenue Improvements

### Construction

Expected construction 2021-2022  
Replacing roundabouts with traffic signals to improve crossing safety

Do Intervention	Units	Emissions Factor	Unit	Sources and notes
<b>Material Quantities Estimate</b>				
Construction Fuel Use Diesel	- L	0.0027	tCO2e/L	MfE 2020
Construction Materials Concrete	179 tonnes	0.11	tCO2e/tonne	AECOM derived factor (See assumptions below)
Steel	67 tonnes	2.85	tCO2e/tonne	MfE 2020
Road Surface Crushed rock or recycled material	- tonnes	0.0032	tCO2e/tonne	IS Calculator NZ v2.0
Gravel	10,531 tonnes	0.0182	tCO2e/tonne	IS Calculator NZ v2.0
Bitumen	- tonnes	0.2966	tCO2e/tonne	IS Calculator NZ v2.0
Asphalt	5,607 tonnes	0.0542	tCO2e/tonne	IS Calculator NZ v2.0
Project Breakdown Total	706 tonnes of CO2e			
<b>Calculated Emissions</b>				
Best estimate of calculated emissions	706 tonnes of CO2e			

### Assumptions

Emissions for construction have been calculated from data provided by Waka Kotahi for this project. When possible assumptions have been made in a consistent manner to ensure comparability. Refer to construction schedule worksheet for indicative schedule of quantities of concrete, steel, aggregates, gravels and fuels used during construction.

Based on previous research for Waka Kotahi, only emissions from the largest emission sources from construction of infrastructure projects have been estimated (concrete, steel, aggregates, asphalt, and on-site fuel use).

Materials and works related to bridge abutments have been included where relevant.

Fuel used in the construction is assumed to be 2 litres of diesel for every m3 of earth works (AECOM derived fuel-use ratio).

The following were not included in the estimate: fuel used in quarrying activity; emissions from the transportation of construction materials to/from site.

Emission factors are sourced from MfE's 2020 Guide (see link below) where appropriate, or from the ISCA-IS Calculator v2.0.

<https://environment.govt.nz/publications/measuring-emissions-detailed-guide-2020/>


The ISCA-IS Calculator v2.0 is available for ISCA members at <https://www.isca.org.au/Tools-and-Resources>

The emission factor for concrete is based on MfE 2020 and ISCA guidance and is based on a standard concrete mix.

**Walnut Avenue Improvements Construction Schedule**

**Source** Schedule of quantities as provided in RFT, prepared by Beca, March 2020. Supplied by WK.

Schedule of Prices				Material Unit		Material Unit		Material Unit		Material Unit		Material Unit		Assumptions/Notes
Code	Description	Quantity	Qty	Concrete	Steel	Asphalt	Aggregates	Fuel						
1	Environmental Compliance	1	LS											
2	Earthworks	1	LS											
3	Ground Improvements	1	LS											
4	Drainage	1	LS											
5	Pavement and Surfacing	1	LS											
6	Bridges	1	LS											
7	Retaining Walls	1	LS											
8	Traffic Services	1	LS											
9	Service Relocations	1	LS											
10	Landscaping	1	LS											
11	Traffic Management and Temporary Works	1	LS											
12	Preliminary and General	1	LS											
13	Extraordinary Construction Costs	1	LS											
14	Dayworks	1	LS											
15	<b>Tender Total</b>													
	<b>On site Overheads</b>													
	On-Site Overheads and Profit are to be included within the rates for Preliminaries & General		Note											
	<b>Off site Overheads and Profit</b>													
	Off-Site Overheads and Profit are to be included within the rates of the Schedule of Prices		Note											
1.00	<b>ENVIRONMENTAL COMPLIANCE</b>													
1.01	Prepare the Contractors Environmental Management Plan (CEMP) & Erosion and Sediment Control Plan	1	LS											
	Updates, implement and maintain the Contractor's Environmental Management Plan (CEMP) & Erosion and Sediment Control Plan and Controls including all temporary works and removal on completion	1	LS											
1.02	TOTAL ENVIRONMENTAL COMPLIANCE													
2.00	<b>EARTHWORKS</b>													
	<b>Site Clearance</b>													
	General site clearance including bushes, undergrowth, fences including foundations, rubbish, debris etc to waste off site - approximately 22 500m <sup>2</sup>	1	LS											
2.01	Remove trees. Including: stumps and root ball and dispose off site	46	no											
	<b>Demolition</b>													
	Break out and dispose off site	1	LS											
2.03	Existing traffic islands. Including: concrete apron / in-fill	1	LS											
2.04	Existing footpath	1	LS											
2.05	Existing kerbs	1	LS											
2.06	Existing concrete rail stop	1	LS											
2.07	Existing gates and take to assigned lay down area	1	LS											
2.08	Existing type C. uminaire. Including: all disconnections, terminations etc.	1	LS											
2.09	Existing type W column. Including: foundation, cabling and disconnections	1	LS											
2.10	Large sign. Including: posts, foundations and power disconnections	1	LS											
2.11	Existing traffic signs. Including: foundation	1	LS											
2.12	Sign 1 (ADS Southbound)	1	LS											
2.13	Sign 2 (ADS Northbound)	1	LS											
2.14	Existing gravel rail stop mound as per drawing 3337200-CE-015 Rev 0	1	LS											
2.15	Remove and dispose of fence off site	1	LS											
2.16	Remove existing line markings	1	LS											
	<b>Earthworks</b>													
2.17	Strip topsoil and stockpile on site - average depth 200mm	290	m <sup>3</sup>					580 l					Assume separate to previous earthworks. Earthworks @ 2l diesel at per m <sup>3</sup> moved	
2.18	Strip topsoil to waste off-site, allow to load, cart and dispose off-site to a managed landfill licensed to accept the typical contaminants as identified in the Detailed Site Investigation	50	m <sup>3</sup>					100 l					Assume separate to previous earthworks. Earthworks @ 2l diesel at per m <sup>3</sup> moved Assuming density of aggregate of 1800kg/m <sup>3</sup> (CI AECOM)	
2.19	Imported GAP65	25	m <sup>3</sup>				45 t						Assuming density of aggregate of 1800kg/m <sup>3</sup> (CI AECOM)	
2.20	Allow to undercut soft or unsuitable material to waste off-site, allow to load, cart and dispose off-site to a managed landfill licensed to accept the typical contaminants as identified in the Detailed Site Investigation	2,093	m <sup>3</sup>				3767.4 t						Assuming density of aggregate of 1800kg/m <sup>3</sup> (CI AECOM)	
2.21	Allow to undercut soft or unsuitable material to waste off-site, allow to load, cart and dispose off-site to a managed landfill licensed to accept the typical contaminants as identified in the Detailed Site Investigation, and fill with GASP65 - Provisional Item	130	m <sup>3</sup>				234 t						Assuming density of aggregate of 1800kg/m <sup>3</sup> (CI AECOM)	
	<b>Imported topsoil</b>													
2.22	Allow to up lift from stockpile and re-spread topsoil	285	m <sup>3</sup>				513 t						Assuming density of aggregate of 1800kg/m <sup>3</sup> (CI AECOM)	
2.23	Extra over for imported topsoil if required - Provisional Item	50	m <sup>3</sup>				90 t						Assuming density of aggregate of 1800kg/m <sup>3</sup> (CI AECOM)	
2.24	Allow to supply materials and construct gabion beds as per specifications and drawings. Includes: prepare subsoil, topsoil and timber batters	215	m <sup>2</sup>				43 l						Assume 100mm thick. Earthworks @ 2l diesel at per m <sup>3</sup> moved.	
	<b>TOTAL EARTHWORKS</b>													
3.00	<b>GROUND IMPROVEMENTS</b>													
4.00	<b>DRAINAGE</b>													
4.01	Abandon stormwater pipes. Allow to plug each end with concrete extending over a minimum of 1m.	2	no										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
4.02	Remove existing manhole and extend pipe on grade to new manhole	1	no										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
4.03	Remove sump cover and vertical pipe. Remove sump covers up to 1m below ground level. Backfill with AP65 to underground pavement level	1	no										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
4.04	Remove existing sumps and abandon stormwater pipe in accordance with drawings and specifications	1	LS											
4.05	Remove sump and sump lead. Backfill and make good surfacing	7	no										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
4.06	Remove existing slot drain	1	LS										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
	<b>Storm Water Drainage</b>													
4.07	Supply and install RCRRJ Class 4 storm-water pipe 300mm dia. Between 0.0m - 1.5m deep	130	m	24.7 t	4.94 t								Estimate provided by AECOM quantity surveyor 19/07/21	
4.08	Supply and install RCRRJ Class 4 storm-water pipe 225 mm dia. Between 0.0m - 1.5m deep	3	m	0.42 t	0.114 t								Estimate provided by AECOM quantity surveyor 19/07/21	
	<b>Works to existing Stormwater</b>													
4.09	Supply and install RCRRJ Class 4 storm-water pipe 150mm dia including direct connection to existing stormwater as CCC CSS SD361 drawings and specifications	5	m	0.5 t	0.19 t								Estimate provided by AECOM quantity surveyor 19/07/21	
	<b>Manholes</b>													
4.10	Supply and install 1050 dia. manhole and base	4	no	8.5 t	0.152 t								Estimate provided by AECOM quantity surveyor 19/07/21	
4.11	0.0m - 1.5m	2	no										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
	<b>Works to Existing Lids, Covers, Grates etc.</b>													
4.12	Allow to raise existing manhole lids to tie into new levels	1	no										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
4.13	0 to 100mm	1	no										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
4.14	250 to 350mm	1	no										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
4.15	500 to 600mm	1	no										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
4.16	Allow to lower existing manhole lids to tie into new levels	2	no										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
4.17	Allow to adjust catch pit grate level to new kerb level	2	no										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
4.18	Allow to adjust fire hydrant / valve pit lid level to tie into new carriageway	7	no										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
4.19	Replace top two DN900 manhole risers and reinstatement existing manhole frame and lid.	1	LS										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
	<b>Sumps</b>													
4.20	Supply and install single sump catch pit complete as drawing 3337200-CE-038 Rev 0	8	no	4.08 t	0.72 t								Estimate provided by AECOM quantity surveyor 19/07/21	
4.21	0.0m - 1.5m and base including cast iron frame and grate and 150mm thick concrete moving strip	3	no	1.53 t	0.27 t								Estimate provided by AECOM quantity surveyor 19/07/21	
4.22	Relocation of existing sump as drawing 3337200-CE-039 and specifications	1	LS										Excluded as likely to immaterial based on previous research for Waka Kotahi.	
4.23	Supply and install subsoil rodding eye and cover	7	no										Excluded as likely to immaterial based on previous research for Waka Kotahi.	



Walnut Avenue Improvements Construction Schedule


Source Schedule of quantities as provided in RFT, prepared by Beca, March 2020. Supplied by WK.

Schedule of Prices				Material Unit		Material Unit		Material Unit		Material Unit		Material Unit		Assumpti ns/ N tes	
Code	Description	Quantity	Qty	C ncrete	t r m3	Steel	t r m3	Asphalt	t r m3	Aggregates	t r m3	Fuel	l r kg		
<b>Kerbings</b>															
4.23	Supply and install kerb and channel as per NZS 4404 2010 (Drawing 3337200-CE-36). Including; 150mm AP40 M4 sub-base compacted to TNZ B/2	800	m	80	t	1.5104	t								Aggregate element included only. Estimate provided by AECOM quantity surveyor 19/07/21
4.24	Supply and install heavy commercial drop kerb. Including; 150mm AP40 M4 sub-base compacted to TNZ B/2	23	m	2.256	t	0.04259328	t								Aggregate element included only. Estimate provided by AECOM quantity surveyor 19/07/21
4.25	Supply and install vehicle kerb crossing. Include to tie into existing (Drawings 3337200-CE-026, 036, 037 & 038)	6	m	0.6	t	0.011328	t								Estimate provided by AECOM quantity surveyor 19/07/21
4.26	Break out and remove existing kerb and replace with vehicle kerb crossing - Refer drawing 3337200-CE-291	20	m	2	t	1.5104	t								Estimate provided by AECOM quantity surveyor 19/07/21
4.27	Supply and install subsoil drains below new kerb and channel at ubg de	830	m												Excluded as likely to immaterial based on previous research for Waka Kotahi
4.28	specifications	30	m	3	t	0.1896	t								19/07/21
<b>Grassed Swales</b>															
<b>South basin and swale as drawings 333 200 CE 064 Rev 0 and 3337200 CE 081 Rev 0 (forming, topsoil and grass seeding measured elsewhere)</b>															
4.29	Supply and install 100 dia HDPE smooth bore punched subsoil drain, 5-8mm pea gravel with no fines, non-woven geotextile in accordance with TNZ F/7 Filtration Class 1; Class B Strength.	60	m												Excluded as likely to immaterial based on previous research for Waka Kotahi.
4.30	Supply and install 100 dia HDPE smooth bore punched subsoil drain, non-woven geotextile in accordance with TNZ F/7 Filtration Class 1; Class B Strength	30	m												Excluded as likely to immaterial based on previous research for Waka Kotahi.
<b>North basin and swale as drawings 333 200 CE 065 Rev 0 and 3337200 CE 081 Rev 0 (forming, topsoil and grass seeding to swale measured elsewhere)</b>															
4.31	Supply and install 100 dia HDPE smooth bore punched subsoil drain, 5-8mm pea gravel with no fines, non-woven geotextile in accordance with TNZ F/7 Filtration Class 1; Class B Strength.	40	m												Excluded as likely to immaterial based on previous research for Waka Kotahi.
4.32	Supply and install 100 dia HDPE smooth bore punched subsoil drain, non-woven geotextile in accordance with TNZ F/7 Filtration Class 1; Class B Strength	15	m												Excluded as likely to immaterial based on previous research for Waka Kotahi.
<b>Soakaway Field</b>															
4.33	95 - 150 washed boulders	210	m3							336.42	t				Assume crushed rock. Rip Rap 1602kg/m3
<b>TOTAL DRAINAGE</b>															
<b>5.00 PAVEMENT AND SURFACING</b>															
<b>State Highway</b>															
<b>Overlay Pavement 1a</b>															
5.01	Allow to mill existing pavement to 250mm	3,590	m2							1615.5	t				Assuming density of aggregate of 1800kg/m3 (CI AECOM)
5.02	Supply and place grade 3 chip seal	3,590	m2					538.5	t						Assuming 0.1m deep and 1.5/m3
5.03	Supply and place 200mm AC20 asphalt concrete	3,590	m2					1077	t						1.5/m3
5.04	Supply and place 50mm SMA 10 wearing course (PSV56), including tack coat as required	3,590	m2					269.25	t						1.5/m3
<b>Overlay Pavement 2a</b>															
5.05	Allow to mill existing pavement to 240mm	3,270	m2							1412.64	t				Assuming 0.1m deep and 1.5/m3
5.06	Supply and place 190 NZTA M4 AP40 basecourse + 1.5% cement	625	m3					93.75	t						Assuming 0.1m deep and 1.5/m3
5.07	Supply and place grade 3 chip seal	3,270	m2					490.5	t						Assuming 0.1m deep and 1.5/m3
5.08	Supply and place 50mm SMA 10 wearing course (PSV56), including tack coat as required	3,270	m2					245.25	t						1.5/m3
<b>Widening Pavement Pavement 1b</b>															
5.09	Allow for sub-grade preparation and testing	1,430	m2												57 l
5.10	Supply and install geogrid and geotextile in base of excavation	1,430	m2												Assume separate to previous earthworks. Earthworks @ 2l diesel at per m3 moved
5.11	Supply and place 200mm NZTA M4 AP40 basecourse	290	m3							522.00	t				Exclude as polymer (plastic), likely to be immaterial based on previous research for Waka Kotahi
5.12	Supply and place grade 3 chip seal	1,430	m2					214.5	t						Assuming density of aggregate of 1800kg/m3 (CI AECOM)
5.13	Supply and place 200mm AC20 asphalt concrete	1,430	m2					429	t						Assuming 0.1m deep and 1.5/m3
5.14	Supply and place 50mm SMA 10 wearing course (PSV56), including tack coat as required	1,430	m2					107.25	t						1.5/m3
<b>Widening Pavement Pavement 2b</b>															
5.15	Allow for sub-grade preparation and testing	1,275	m2												510 l
5.16	Supply and install geogrid and geotextile in base of excavation	1,275	m2												Assume separate to previous earthworks. Earthworks @ 2l diesel at per m3 moved
5.17	Supply and place 295mm AP65 sub-base	375	m3							675.00	t				Exclude as polymer (plastic), likely to be immaterial based on previous research for Waka Kotahi
5.18	Supply and place 190 NZTA M4 AP40 basecourse + 1.5% cement	245	m3					36.0	t						Assuming density of aggregate of 1800kg/m3 (CI AECOM)
5.19	Supply and place grade 3 chip seal	1,275	m2					91.25	t						Assuming 0.1m deep and 1.5/m3
5.20	Supply and place 50mm SMA 10 wearing course (PSV56), including tack coat as required	1,275	m2					96.625	t						1.5/m3
<b>East Street / Walnut Avenue</b>															
<b>Overlay Pavement 3a</b>															
5.21	Allow to mill existing pavement to 210mm	1,400	m2							529.2	t				Assuming density of aggregate of 1800kg/m3 (CI AECOM)
5.22	Supply and place grade 3 chip seal	1,400	m2					210	t						Assuming 0.1m deep and 1.5/m3
5.23	Supply and place 160mm AC20 asphalt concrete	1,400	m2					336	t						1.5/m3
5.24	Supply and place 50mm SMA 10 wearing course (PSV56), including tack coat as required	1,400	m2					105	t						1.5/m3
<b>Overlay Pavement 4a</b>															
5.25	Allow to mill existing pavement to 220mm	1,910	m2							756.36	t				Assuming density of aggregate of 1800kg/m3 (CI AECOM)
5.26	Supply and place 170mm NZTA M4 AP40 basecourse + 1.5% cement	325	m3					82.875	t						1.5/m3
5.27	Supply and place grade 3 chip seal	2,230	m2					334.5	t						Assuming 0.1m deep and 1.5/m3
5.28	Supply and place 50mm SMA 10 wearing course (PSV56), including tack coat as required	1,910	m2					143.25	t						1.5/m3
<b>Widening Pavement Pavement 3b</b>															
5.29	Allow for sub-grade preparation and testing	64	m2												25.6 l
5.30	Supply and place geogrid and geotextile in base of excavation	64	m2												Assume separate to previous earthworks. Earthworks @ 2l diesel at per m3 moved
5.31	Supply and place 200mm NZTA M4 AP40 basecourse	15	m3							5.94	t				Exclude as polymer (plastic), likely to be immaterial based on previous research for Waka Kotahi
5.32	Supply and place grade 3 chip seal	64	m2					9.6	t						Assuming density of aggregate of 1800kg/m3 (CI AECOM)
5.33	Supply and place 160mm AC20 asphalt concrete	64	m2					15.36	t						Assuming 0.1m deep and 1.5/m3
5.34	Supply and place 50mm SMA 10 wearing course (PSV56), including tack coat as required	64	m2					4.8	t						1.5/m3
<b>Widening Pavement Pavement 4b</b>															
5.35	Allow for sub-grade preparation and testing	230	m2												92 l
5.36	Supply and place geogrid and geotextile in base of excavation	230	m2												Assume separate to previous earthworks. Earthworks @ 2l diesel at per m3 moved
5.37	Supply and place 290mm AP65 sub-base	55	m3							28.71	t				Exclude as polymer (plastic), likely to be immaterial based on previous research for Waka Kotahi
5.38	Supply and place 170 NZTA M4 AP40 basecourse + 1.5% cement	35	m3					52.5	t						Assuming density of aggregate of 1800kg/m3 (CI AECOM)
5.39	Supply and place grade 3 chip seal	230	m2					34.5	t						Assuming 0.1m deep and 1.5/m3
5.40	Supply and place 50mm SMA 10 wearing course (PSV56), including tack coat as required	230	m2					17.25	t						1.5/m3
<b>Concrete Commercial Vehicle Crossing</b>															
5.41	Allow to form new concrete commercial vehicle crossing complete, as drawings and specifications	120	m2	45	t										Assuming 0.15m depth at 2.5/m3
<b>Saw cutting</b>															
5.42	Allow to saw out and tie in existing pavements	200	m												Likely to be immaterial based on previous research for Waka Kotahi
5.43	Crack bandage to interface of new and existing pavements	200	m												Likely to be immaterial based on previous research for Waka Kotahi
<b>Others</b>															
5.44	Extra over for supply and place 50mm SMA 10 wearing course where higher PSV is required (from PSV56 to PSV70)	2,975	m2					223.125	t						Likely to be immaterial based on previous research for Waka Kotahi
<b>TOTAL PAVEMENT AND SURFACING</b>															
<b>6.00 BRIDGES</b>															
<b>7.00 RETAINING WALLS</b>															
<b>8.00 TRAFFIC SERVICES</b>															
<b>Road markings in accordance with NZTA Manual of Traffic Signs and Markings, Part II - Markings and TPC Manual</b>															
<b>Temporary Road Markings</b>															
<b>White reflectorised line marking</b>															
8.01	Border line; 100mm wide	1,815	m												Likely to be immaterial based on previous research for Waka Kotahi
8.02	Centre line; 100mm wide continuous line	315	m												Likely to be immaterial based on previous research for Waka Kotahi
8.03	Centre line; 100mm wide 3m stripe 7m gap	680	m												Likely to be immaterial based on previous research for Waka Kotahi
8.04	Continuity line; 100mm wide, 1m stripe, 3m gap	95	m												Likely to be immaterial based on previous research for Waka Kotahi
8.05	Crossing line; 100mm wide	295	m												Likely to be immaterial based on previous research for Waka Kotahi
8.06	Edgeline; 100mm wide	870	m												Likely to be immaterial based on previous research for Waka Kotahi
8.07	Limit line; 300 wide	110	m												Likely to be immaterial based on previous research for Waka Kotahi
8.08	Median bar; 600 wide	300	m												Likely to be immaterial based on previous research for Waka Kotahi
<b>Yellow reflectorised line marking</b>															

**Walnut Avenue Improvements Construction Schedule**

**Source** Schedule of quantities as provided in RFT, prepared by Beca, March 2020. Supplied by WK.


Schedule of Prices		Material Unit		Material Unit		Material Unit		Material Unit		Material Unit		Assumptions/ Notes	
Code	Description	Quantity	Qty	Concrete	Form	Steel	Form	Asphalt	Form	Aggregates	Form	Fuel	Form
8.09	No stopping; 100mm wide, 1m stripe, 2m gap	1,415	m										
8.10	100mm wide yellow border and cross hatching to level crossing	190	m2										
<b>Permanent Road Markings</b>													
<b>White reflectorised line marking</b>													
8.11	Border line; 100mm wide	1,815	m										
8.12	Centre line; 100mm wide	320	m										
8.13	Centre line; 100mm wide, continuous line; 3m stripe, 7m gap	680	m										
8.14	Continuity line; 100mm wide; 1m stripe; 3m gap	95	m										
8.15	Crossing line; 100mm wide	295	m										
8.16	Edgeline; 100mm wide	870	m										
8.17	Limit line; 300 wide	110	m										
8.18	Median bar; 600 wide	300	m										
<b>Yellow reflectorised line marking</b>													
8.19	No stopping; 100mm wide, 1m stripe, 2m gap	1,415	m										
8.20	100mm wide yellow border and cross hatching to level crossing	190	m2										
<b>Green pavement marking</b>													
8.21	Cycleway Surface Marking	1,065	m2										
<b>Symbols, Lettering etc</b>													
8.22	Cycle lane symbol	65	no										
8.23	Directional arrow; combined	10	no										
8.24	Directional arrow; left turn	11	no										
8.25	Directional arrow; right turn	23	no										
8.26	Directional arrow; straight	13	no										
8.27	Fire hydrant	7	no										
8.28	Lettering "X RAIL"	4	no										
8.29	RRPMs	141	no										
8.30	Kerb top markers; yellow monodirectional	96	no										
<b>Road signs, gantries</b>													
Supply and installation of new signs inclusive of foundations, all in accordance with drawings and specifications.													
8.31	Sign 1 (ADS South bound)	1	no										
8.32	Sign 2 (ADS North bound)	1	no										
8.33	3a (re-use existing Christchurch to the right)	1	no										
8.34	4b (re-use existing Allenton to the right)	1	no										
8.35	5a (re-use existing Timaru to the left)	1	no										
8.36	5b (re-use existing Timaru to the right)	1	no										
8.37	6b (re-use existing Town Centre to the Right)	1	no										
8.38	PW-3	7	no										
8.39	PW-43.3	2	no										
8.40	RG-7	1	no										
8.41	RG-12	1	no										
8.42	600 dia arrow disc sign; RG-17	14	no										
8.43	Sign 7	1	no										
8.44	Sign WXL1	2	no										
8.45	Sign WXR1	2	no										
8.46	Sign WX1-L	2	no										
8.47	Sign WX1-R	2	no										
Supply and installation of new signs fixed to fence/gate, all in accordance with drawings and specifications.													
8.48	600 x 600mm "LOOK FOR TRAINS" sign; WX8 (a)	8	no										
8.49	600 x 600mm "EMERGENCY EXIT PLEASE PUSH GATE" sign; Emergency Exit Gate (b)	4	no										
8.50	600 x 600mm "EMERGENCY EXIT" sign; Directional Emergency Exit (left) (d)	2	no										
8.51	600 x 600mm "EMERGENCY EXIT" sign; Directional Emergency Exit (right) (e)	2	no										
8.52	600 dia "NO ENTRY" disc sign; RG-9 (c)	4	no										
<b>Traffic signals</b>													
Supply and installation of new traffic signals in accordance with drawings and specifications.													
8.53	200mm 6 Aspect Lantern with closed visor	16	no										
8.54	200mm 6 Aspect Lantern with open visor	17	no										
8.55	300mm 6 Aspect Lantern with closed visor	2	no										
8.56	300mm 6 Aspect Lantern with open visor	2	no										
8.57	Pedestrian Lantern	12	no										
8.58	Pedestrian push button	12	no										
<b>SCATS Connection</b>													
Allowance for installation of SCATS system, testing and connection to the SCATS system to Traffic Operations Centre (WTOC) (Including connection with adjacent intersection)													
8.59		1	LS										
8.60	Supply and install CCTV cameras	2	no										
8.61	Supply and install Fibre connection with comms (including connection with adjacent intersection and level crossing)	1	LS										
8.62	Allowance for spare ethernet cable to CCTV and communication devices	1	LS										
<b>Poles</b>													
Supply and install poles including retention socket connections, earthing and cabling													
8.63	Supply and install pole - Type 1. Including foundation	5	no										
8.64	Supply and install pole - Type 7. Including foundation	2	no										
8.65	Supply and install pole - Type 8. Including foundation	8	no										
<b>Ducting</b>													
Supply and install 1no. 100 dia. orange uPVC duct, laid in trench 0.6 - 1m deep, including all bedding, joints, connections, backfill and draw wires (from access chambers to poles)													
8.66		175	m										
Supply and install 3no. 100 dia. orange uPVC duct, laid in trench 0.6 - 1m deep, including all bedding, joints, connections, backfill and draw wires (between access chambers)													
8.67		370	m										
Supply and install 1no. 50 dia. orange uPVC duct, laid in trench minimum 300mm, including all bedding, joints, connections, backfill and draw wires (from access chambers to kerbside junction box)													
8.68		110	m										
<b>Loop Feeders</b>													
Supply and install loop feeder cables from control cabinets to kerbside junction boxes (assumes 2 pair loop feeder cable)													
8.69		1,105	m										



Walnut Avenue Improvements Construction Schedule

Source Schedule of quantities as provided in RFT, prepared by Beca, March 2020. Supplied by WK.

Schedule of Prices				Material Unit		Material Unit		Material Unit		Material Unit		Material Unit		Assumptions/Notes	
Code	Description	Quantity	Qty	Concrete	m <sup>3</sup>	Steel	t	Asphalt	m <sup>3</sup>	Aggregates	m <sup>3</sup>	Fuel	l	kg	
<b>Detection Loop</b>															
8.70	Supply and install Vehicle Detector Loop	24	no												Likely to be immaterial based on previous research for Waka Kotahi
8.71	Supply and install Cycle Detector Loop	6	no												Likely to be immaterial based on previous research for Waka Kotahi
8.72	Supply and install Queue Detector Loop	5	no												Likely to be immaterial based on previous research for Waka Kotahi
<b>Controllers</b>															
8.73	Supply and install 20 group Aldridge ATSC4 ELV Traffic Signal Controllers with VC6 compliance	2	no												Likely to be immaterial based on previous research for Waka Kotahi
8.74	Allow for commissioning	1	LS												Likely to be immaterial based on previous research for Waka Kotahi
<b>Power Connection</b>															
8.75	Supply, install and terminate power cable into traffic control cabinets. (2no.)	1	LS												Likely to be immaterial based on previous research for Waka Kotahi
<b>Traffic Signal Equipment</b>															
<b>Access Chambers</b>															
8.76	Supply and install concrete Access Chambers with lid 1.5m deep	29	no												Likely to be immaterial based on previous research for Waka Kotahi
<b>Junction Boxes</b>															
8.77	Supply and install Kerbside Junction Box behind kerb.	11	no												Likely to be immaterial based on previous research for Waka Kotahi
<b>Multi core cable</b>															
8.78	Supply and install orange 36 core cable from controllers to poles	880	m												Likely to be immaterial based on previous research for Waka Kotahi
<b>Lighting</b>															
Supply and install street lighting columns including cast-in foundations, connections and earthing. Energy absorbing octagonal sectional steel column with m.tred. outreach. 10m mounting height. 3m outreach.															
8.79	Column Type Z Energy absorbing octagonal sectional steel column with m.tred. outreach. 12m mounting height. 3m outreach.	23	no			17.25	t								No data available. Estimate provided by AECOM quantity surveyor 19/07/21
8.80	Column Type V Supply and install Juma / JUSP octagonal sectional column with m.tred. outreach. 10m mounting height. 3m outreach. including all foundations, connections, cabling and earthing	5	no			3.75	t								Estimate provided by AECOM quantity surveyor 19/07/21
8.81	Column Type X Existing column to be retained.	8	no												Likely to be immaterial based on previous research for Waka Kotahi
8.82	Column Type Y Existing column to be retained.	11	no												Likely to be immaterial based on previous research for Waka Kotahi
8.83	Type A Supply and install luminaire as per Specifications and Drawings	3	no												Likely to be immaterial based on previous research for Waka Kotahi
8.84	Type D - TRANSLEDER TL-B-2-V-068-06-SC-PL-8510LM 4000K LED LUMINAIRE	17	no												Likely to be immaterial based on previous research for Waka Kotahi
8.85	Type E - TRANSLEDER TL-B-2-V-098-06-SC-PL-12110LM 4000K LED LUMINAIRE	12	no												Likely to be immaterial based on previous research for Waka Kotahi
8.86	Type G - TRANSLEDER TL-B-3-V-151-09-SC-PL-17200LM 4000K LED LUMINAIRE	4	no												Likely to be immaterial based on previous research for Waka Kotahi
8.87	Type H - TRANSLEDER TL-B-3-V-125-09-SC-PL-15000LM 4000K LED LUMINAIRE	4	no												Likely to be immaterial based on previous research for Waka Kotahi
8.88	Type K - TRANSLEDER TL-B-2-V-068-06-SC-PL-8810LM 4000K LED LUMINAIRE	5	no												Likely to be immaterial based on previous research for Waka Kotahi
8.89	Type L - TRANSLEDER TL-B-2-V-098-06-SC-PL-12110LM 4000K LED LUMINAIRE	2	no												Likely to be immaterial based on previous research for Waka Kotahi
<b>TOTAL TRAFFIC SERVICES</b>															
<b>SERVICES RELOCATIONS</b>															
9.00	Main Contractor to allow for trenching / earthworks (assume 30m, 1m deep trench) for the substation relocation and associated works. To include for attendance during works, traffic management.	1	LS												
9.01	Main Contractor to allow for 1m deep trench for Chorus cable relocation. Liaise with Chorus to execute. (Item 9.03)	10	m									40	l		Assume 2m wide trench. Earthworks @ 2l diesel at per m <sup>3</sup> moved
9.02	Relocate existing Chorus pit to new boundary position including trench.	-	LS												
<b>Electrical Cable</b>															
9.04	Main contractor to allow for trenching (including backfill) to electrical works, take possession of free issued duct and install in trench.		Note												
9.04.1	Trench as per EA Networks drawings WU1058a Sheet 5 Detail Section A	12	m									24	l		Assume 1m wide, 1m deep trench. Earthworks @ 2l diesel at per m <sup>3</sup> moved
9.04.2	Trench as per EA Networks drawings WU1058a Sheet 5 Detail Section B	115	m									460	l		Assume 1m wide, 1m deep trench. Earthworks @ 2l diesel at per m <sup>3</sup> moved
9.04.3	Trench as per EA Networks drawings WU1058a Sheet 5 Detail Section C	18	m									72	l		Assume 1m wide, 1m deep trench. Earthworks @ 2l diesel at per m <sup>3</sup> moved
9.04.4	Trench as per EA Networks drawings WU1058a Sheet 5 Detail Section D, E	60	m									240	l		Assume 1m wide, 1m deep trench. Earthworks @ 2l diesel at per m <sup>3</sup> moved
9.04.5	Trench as per EA Networks drawings WU1058a Sheet 5 Detail Section F, G, H	60	m									640	l		Assume 1m wide, 1m deep trench. Earthworks @ 2l diesel at per m <sup>3</sup> moved
9.04.6	Trench as per EA Networks drawings WU1058a Sheet 5 Detail Section I	15	m									60	l		Assume 1m wide, 1m deep trench. Earthworks @ 2l diesel at per m <sup>3</sup> moved
9.04.7	Trench as per EA Networks drawings WU1058a Sheet 5 Detail Section Typical trench Stations (SL and LV Cables) Scope not yet defined between EA Networks and design documentation (Provisional Sum)	53	m									2148	l		Assume 1m wide, 1m deep trench. Earthworks @ 2l diesel at per m <sup>3</sup> moved
9.05	Relocation of Services Relocation of unknown existing services not covered by earlier Documentation (Gas, electrical and comms) - Provisional sum	1	PS												N/A
9.06	Protection of Services Liaise with service providers to execute identification / stand over / direct service provision.	1	PS												N/A
9.07	Service Investigation - locate, protect, survey and record existing services. Additional hydro excavation to confirm design including but not limited to record / survey physical location of existing service at every excavated pothole. By Engineer's instructions only. Provisional Sum	1	LS												N/A
9.08	Liaise with service providers, service protection and relocation including stand over, identification and direct costs of unknown services / service clashes - Provisional Sum	1	PS												N/A
9.09	<b>TOTAL SERVICE RELOCATIONS</b>	1	PS												N/A
<b>10.00 LANDSCAPING</b>															
<b>Grassing, hydro seeding, planting, re-vegetation, mulch</b>															
10.01	Grass seeding	2,440	m <sup>2</sup>												N/A
<b>Fencing</b>															
10.02	Supply and install 1.2m high galvanneal chain-link fence on grade including 200 dia 20MPa concrete footing as drawing 3337200-CE-280 Rev 0	275	m			20.625	t								Estimate provided by AECOM quantity surveyor 19/07/21
<b>Asphalt Footpaths</b>															
10.03	7 CCC t bills AP20 r TNZ M 4 AP20	80	m <sup>3</sup>					120	t						1.5t/m <sup>3</sup>
10.04	NZTA M10 D67 Supply and install 150 x 25mm H4 timber edge batten with 50 x 50 x 600mm H4 timber pegs at 1m centres	740	m <sup>2</sup>					1110	t						1.5t/m <sup>3</sup>
10.05	Pram crossings	250	m												N/A
10.06	Supply and install tactile pavers	12	no												N/A
10.07	Supply and install tactile pavers	40	m <sup>2</sup>												Assuming 0.15m depth at 2.5t/m <sup>3</sup>
<b>Traffic Islands</b>															
10.08	Supply and install Pedestrian Islands. Including, kerb, nosing and concrete infill (Drawings 3337200-CE-236)	550	m <sup>2</sup>												N/A
<b>TOTAL LANDSCAPING</b>															
<b>11.00 TRAFFIC MANAGEMENT AND TEMPORARY WORKS</b>															
11.01	Prepare Contractor's Temporary Traffic Management Plan Implement and maintain the Contractor's temporary traffic management plan including temporary works and removal on completion	1	LS												N/A
11.02	<b>TOTAL TRAFFIC MANAGEMENT AND TEMPORARY WORKS</b>	1	LS												N/A
<b>12.00 PRELIMINARY AND GENERAL</b>															
<b>Survey</b>															
12.01	Survey, set out & verify design Fixed costs	1	LS												N/A
12.02	Site establishment	1	LS												N/A
12.03	Site demobilisation / Clean up	1	LS												N/A
12.04	Contract insurances	1	LS												N/A
12.05	Project Signboards	1	LS												N/A
12.06	Pr g m	1	LS												N/A
12.07	Specification	1	LS												N/A
12.08	Health and Safety As-built drawings, Operation, Maintenance manuals, Producer Statements and RAMM data.	1	LS												N/A
12.09	Statements and RAMM data.	1	LS												N/A
12.10	KiwiRail compliance and liaison	1	LS												N/A



**Walnut Avenue Improvements Construction Schedule**

**Source** Schedule of quantities as provided in RFT, prepared by Beca, March 2020. Supplied by WK.

Schedule of Prices			Material Unit		Material Unit		Material Unit		Material Unit		Assumptions/Notes		
Code	Description	Quantity	Qty	Concrete	Steel	Asphalt	Aggregates	Fuel	Other				
12.11	Network Maintenance	1	LS							N/A			
12.12	Reporting	1	LS							N/A			
12.13	Allow for any items not included above that the contractor deems necessary to complete the works	1	LS							N/A			
<b>TOTAL PRELIMINARY AND GENERAL</b>													
<b>13.00 EXTRAORDINARY CONSTRUCTION COSTS</b>													
<b>KiwiRail Works</b>													
13.01	Cut yard track and remove to assigned railway down area including all items down to sub-base level; all works in accordance with drawing 3337200-CE-015, specifications and KiwiRail requirements	1	LS							N/A			
13.02	Demolition of existing KiwiRail Depot Building including all slabs and foundations, termination of services and disposal off site - approximately 245m <sup>2</sup>	1	LS							N/A			
<b>New KiwiRail Depot Building</b>													
13.03	New KiwiRail Depot Building - 30m by 8.4m in accordance with Drawing CE-291 and scope of works as per Schedule 5	1	PS							N/A			
13.04	1.3m high galvannead chainlink fence including appropriate stays and posts founded in concrete footings	208	m		15.6					Estimate provided by AECOM quantity surveyor 19/07/21			
13.05	Vehicle gates - up lift existing KiwiRail depot compound gates, store and reinstall including mounting to new gate posts (Drawing CE-291)	2	no							N/A			
13.06	Pedestrian gate - supply and install new 1.2m wide chain link gate	1	no							N/A			
<b>Temporary Depot Works</b>													
13.07	room in accordance with Drawing CE-291 and scope of temporary works as per Schedule 5 until receipt of the Code of Compliance for the new permanent depot including relocation from old depot into the temporary depot and from temporary depot to the new permanent depot and including provision (and later disconnection) of all necessary temporary services such as power, waste water, water, data, etc. until receipt of Code of Compliance for the new permanent depot.	1	LS							N/A			
<b>TOTAL EXTRAORDINARY CONSTRUCTION COSTS</b>													
<b>14.00 DAYWORKS</b>													
All items in this section are PROVISIONAL													
<b>Labour</b>													
14.01	Skilled (e.g. Labourer or Concrete worker)	200	hr							N/A			
14.02	Drain layer	200	hr							N/A			
14.03	Leading hand	200	hr							N/A			
14.04	Working foreman	200	hr							N/A			
14.05	Traffic management crew	200	hr							N/A			
14.06	Mobile closure	20	day							N/A			
14.07	Semi-static closure	20	day							N/A			
14.08	Lane closure	20	day							N/A			
14.09	Shoulder closure	20	day							N/A			
14.10	VMS	20	day							N/A			
<b>Plant (Provisional)</b>													
14.12	latest edition of the Civil Contractors New Zealand Plant Hire Rates (The Blue Book) and calculate the total amount into the tender amount (e.g. \$10,000 x 90% = \$9,000 total). Note that Blue Book rates are inclusive of the cost of fuel, maintenance, repairs, machine operator, on-site Overheads and Off-site Overheads and Profit.	20,000	%							N/A			
<b>Working Day Rate</b>													
14.13	Rate per working day (PROVISIONAL)	20	day							N/A			
<b>Valuation of Variations from Net Costs</b>													
14.14	Allow the Provisional Sum for Variations to be valued from Net Costs	1	PS							N/A			
14.15	% for On-site Overheads applicable to Variations to be valued from New Costs (Provisional Item)	200,000	%							N/A			
14.16	% for Off-site Overheads applicable to Variations to be valued from New Costs (Provisional Item)	200,000	%							N/A			
<b>TOTAL DAYWORKS</b>													
				179	1	67	1	6,587	1	10,531	1	5,607	1

PROACTIVELY RELEASED BY  
 TE MANATŪ WAKA MINISTRY OF TRANSPORT